

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01669-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 6-18S-10W
4915 feet from S Section Line, 5021 feet from E Section Line
Lease Name: AMES P Well #: 2
County: RICE Total Vertical Depth: 3057 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

PROD Size: 7 feet: 3045 110 SX CMT
SURF Size: 10.75 feet: 163 140 SX CMT

\$ 99³⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2004 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed (NOTE: ESTIMATED CASING LEAK @ 2600').
Plugging CIBP @ 2950'.
Method: Shot pipe perms 1250' & 50 sxs; 850' & 50 sxs; and 300' to 0'.

RECEIVED
KCC DISTRICT #2
SEP 21 2004

Plugging Proposal Received By: JACK LUTHI WitnessType: PARTIAL
Date/Time Plugging Completed: 09/10/2004 5:00 PM KCC Agent: JACK LUTHI

WICHITA, KS

Actual Plugging Report:

Perforated casing at 1250' and pumped 50 sacks of cement. Perforated casing at 850' and pumped 50 sacks of cement. Perforated at 300' and circulated cement to surface. Fell 100'; came back and filled to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2983	2993		

RECEIVED
OCT 2004
KCC WICHITA

Remarks: ALLIED CEMENT

Plugged through: TBG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE 10-6-04

TEL. NO. 2005060609