

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20186-00-00
Spot: SENENE Sec/Twnshp/Rge: 17-19S-10W
990 feet from N Section Line, 330 feet from E Section Line
Lease Name: MANSZ Well #: 3-D
County: RICE Total Vertical Depth: 3325 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W. 6TH ST
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3319 100 SX CMT
SURF Size: 8.625 feet: 215 225 SX CMT

108⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2004 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 3028' & 5 sxs common; 1300' & 35 sxs; 850' & 35 sxs; and 265' - 0'.

RECEIVED
KCC DISTRICT #2
SEP 21 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2004 4:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Cut 5-1/2" casing off at 1700'. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled to 265' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3319	3336		Arbuckle OH
3180	3184		
3146	3150		
3078	3080		

RECEIVED
OCT 23 2004
KCC WICHITA

Remarks: ALLIED #20101

Plugged through: CSG

District: 02

Signed

Jack Luthi
(TECHNICIAN)

INVOICED

DATE

10-6-04

UV. NO.

2005060607