

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22044-00-00

Spot: SW

Sec/Twnshp/Rge: 1-21S-7W

1320 feet from S Section Line,

1320 feet from W Section Line

Lease Name: BROTHERS

Well #: 10-1

County: RICE

Total Vertical Depth: 3572 feet

Operator License No.: 4419

Op Name: BEAR PETROLEUM, INC.

Address: PO BOX 438

HAYSVILLE, KS 67060

CIBP Size: feet: 3225

PROD Size: 5.5 feet: 3563 175 SX CMT

SURF Size: 8.625 feet: 210 223 SX CMT

#116 09

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/08/2004 10:00 AM

Plug Co. License No.: 3004

Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.

Proposal Rcvd. from: JOE

Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed  
Plugging  
Method:

CIBP @ 3225' & 2 sxs of common; 1063' & 35 sxs; 645' & 35 sxs; and 265' - 0'.

RECEIVED  
KCC DISTRICT #2

SEP 21 2004

WICHITA, KS

Plugging Proposal Received By: JACK LUTHI

WitnessType: NONE

Date/Time Plugging Completed: 09/08/2004 2:30 PM

KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3225' and 2 sacks of common cement. Cut casing off at 1304'. Pulled to 1063' and pumped 35 sacks of cement. Pulled to 645' and pumped 35 sacks of cement. Pulled to 265' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3476	3498		
3181	3193		

RECEIVED  
OCT 06 2004  
KCC WICHITA

Remarks: COPELAND #24273

Plugged through: CSG

District: 02

Signed

Jack L Luthi

(TECHNICIAN)

INVOICED

DATE

10-6-04

WEL. NO.

2005060605