

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00892-00-00
Spot: NESENE Sec/Twnshp/Rge: 28-22S-15W
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: O E SMITH A Well #: 1
County: PAWNEE Total Vertical Depth: 3992 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

CIBP Size: feet: 3970
PROD Size: 7 feet: 3989 WITH 150 SX CMT
SURF Size: 10.75 feet: 206 WITH 150 SX CMT

74
\$129

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2004 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3820' & 7 SX CMT. PLUG AT 960' WITH 20 SX GEL & 75 SX CMT. PLUG AT 240' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2004 1:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3970'. SANDED TO 3820' & 7 SX CMT. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 960' WITH 20 SX GEL - 75 SX CMT. 2ND PLUG AT 240' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3980	3987		
3950	3962		

RECEIVED
OCT 13 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 7" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED
DATE 10-13-04
INV. NO. 2005060646

[Signature]