

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20231-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 13-20S-23W  
1980 feet from S Section Line, 660 feet from W Section Line  
Lease Name: MARANVILLE B Well #: 2  
County: NESS Total Vertical Depth: 4359 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: PO BOX 70 234 W. 11TH, STE A  
HAYS, KS 67601

PROD Size: 5.5 feet: 4350 WITH 125 SX CMT  
SURF Size: 8.625 feet: 282 WITH 175 SX CMT

*141 67*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2004 10:20 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: RUN TUBING TO 4300' & 25 SX CMT & 200# HULLS. PLUG AT 1500'. PLUG AT 900' WITH 40 SX CMT. PERFORATE AT 700'. CIRCULATE TO SURFACE FROM 700' WITH TUBING.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2004 2:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

PBTD 4359'. RUN TUBING TO 4300' & PUMP 25 SX COMMON CMT WITH 3% CC & 100# HULLS. PULL TUBING TO 1500' & PUMP 40 SX COMMON CMT WITH 3% CC. PULL TUBING & WAIT 1 1/2 HOURS. PERFORATE AT 700'. PUMP 150 SX CMT. MAXIMUM PRESSURE 300#. ON VACUUM. TIED ON TO BACKSIDE & PUMP 10 SX CMT. PRESSURED TO 500# & HELD. CHECKED CASING & FOUND CMT DOWN 250'. PUMPED 40 SX CMT.

RECEIVED  
OCT 13 2004  
KCC WICHITA

Remarks: USED COMMON & 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED  
OCT - 5 2004  
KCC Dodge City

Signed

*Michael J. Maier*  
(TECHNICIAN)

INVOICED  
DATE 10-13-04  
INV. NO. 2005060640

*[Signature]*  
Form CP-2/3