

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12789-00-04
Spot: SEWNNE Sec/Twnshp/Rge: 12-25S-13W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: NORTH LEESBURG UNIT Well #: 202
County: STAFFORD Total Vertical Depth: 4127 feet

Operator License No.: 6679
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH
Address: PO BOX 1
OXFORD, KS 67119

CIBP Size: feet: 3640 WITH 6 SX CMT
CIBP Size: feet: 3849
PROD Size: 6 feet: 4117 WITH 250 SX CMT
SURF Size: 10.75 feet: 281 WITH 225 SX CMT

134¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2004 11:00 AM
Plug Co. License No.: 6679 Plug Co. Name: SHORT, W.D. AND MARJORIE D/B/A SHORT, W. D. OIL CO.
Proposal Rcvd. from: DON SHORT Company: W.D. SHORT OIL CO. Phone: (620) 455-3576

Proposed Plugging Method: PERFORATE & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2004 1:34 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3849'. SET CIBP @ 3640' & 6 SX CMT. PERFORATED 6" @ 750'. RAN TUBING TO 763'. PUMPED 50 SX CMT - 200# HULLS - 50 SX CMT CIRCULATING CMT TO SURFACE UP 6" CASING. PULLED TUBING. TOPPED OFF 6" WITH 28 SX CMT. 6" SQUEEZED AT 323' WITH 350 SX CMT. 10 3/4" X 6" ANNULUS FULL OF CMT AT SURFACE.

Perfs:


Top	Bot	Thru	Comments
3761	3771		
3733	3743		
3721	3725		
3690	3697		

RECEIVED
OCT 13 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 10-13-04

INV. NO. 2005060650

Form C-223 *[Signature]*