

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21272-00-00
Spot: SESWNE Sec/Twnshp/Rge: 11-32S-42W
2970 feet from S Section Line, 1657 feet from E Section Line
Lease Name: JACKSON Well #: 4-11
County: MORTON Total Vertical Depth: 5200 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4877 WITH 30 SX CMT
PROD Size: 5.5 feet: 5200 WITH 200 SX CMT
SURF Size: 9.625 feet: 1463 WITH 500 SX CMT

#169⁰⁰

Well Type: GSO UIC Docket No: _____ Date/Time to Plug: 05/25/2004 11:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SERVICES Phone: (303) 595-3331

Proposed Plugging Method: SET CIBP ABOVE PERFS WITH 10 SX CMT. PLUG AT SHOOTOFF POINT WITH 50 SX CMT. PLUG AT 1500' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/25/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 4877' WITH 30 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1670' WITH 125 SX CMT. GOOD CIRCULATION. 2ND PLUG AT 600' WITH 50 SX CMT. GOOD CIRCULATION. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5067	5078		
5027	5034		
5019	5024		
5010	5016		

RECEIVED
OCT 13 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 1700' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 10-13-04
INV. NO. 2005060642

Form CP-2/3