

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20989-00-01
Spot: SWNW Sec/Twnshp/Rge: 1-32S-42W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BAUGHMAN Well #: 1-1
County: MORTON Total Vertical Depth: 5225 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4050 WITH 30 SX CMT
MSCC Size: feet: 3197
PROD Size: 4.5 feet: 5220 WITH 485 SX CMT
SURF Size: feet: 1501 WITH 460 SX CMT

\$ 169 81

Well Type: GSO UIC Docket No: _____ Date/Time to Plug: 06/03/2004 9:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: CIBP @ 4900' WITH 10 SX CMT. PLUG AT SHOOTOFF POINT WITH 75 SX CMT. PLUG AT 1500' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SEST CIBP @ 4900'. WOULD NOT SET. SET CIBP @ 4050' WITH 30 SX CMT. 1ST PLUG AT 1408' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 12 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5100	5105		
5069	5078		
5020	5030		

RECEIVED
OCT 13 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 1408' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 10-13-04
INV. NO. 2005060642

Form SP-2, B