

RECEIVED
OCT 01 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 175-21784-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 12-18-99

Well Operator: ELDER & VAUGHN, INC. KCC License #: 7457
(Owner / Company Name) (Operator's)

Address: P.O. BOX 18938 City: OKLAHOMA

State: OKLAHOMA Zip Code: 73154 Contact Phone: (405) 842-8877

Lease: JACQUART Well #: 1-30 Sec. 30 Twp. 33 S. R. 32 East West

150 - SOUTH - C - W/2 Spot Location / QQQQ County: SEWARD

2490 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3960 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 0 Set at: - Cemented with: - Sacks

Surface Casing Size: 8 5/8 Set at: 598 Cemented with: 850 Sacks

Production Casing Size: 4 1/2 Set at: 2776 Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2674-82, CIBP @ 2660, 2635-43 & 2613-20

2797 / Elevation: 2802 (G.L. / K.B.) T.D.: 2779 P.BTD: 2660 Anhydrite Depth: 1530-1610
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Rods & tbg. stuck by Glorietta sd & could not pull. cut tbg off @ 1000' - will set cement plug (hulls & 50 sks cement) on top of fish @ approx. 1000' w.o.c. then tag plug. Spot 50 sk plug @ bottom of surface csq., 30 sks @ 300' and 15 sks 40' to surface - Pull & lay down 4 1/2" csq.

As per KCC rules and regulations

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? SENT IN WITH ORIGINAL ACO-1 FORM

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: JACK H. VAUGHN
ELDER & VAUGHN, INC. Phone: (405) 842-8877

Address: P.O. BOX 18938 City / State: OKLAHOMA CITY, OK 73154

Plugging Contractor: SARGENT & HORTON PLUGGING, INC. KCC License #: 31151
(Company Name) (Contractor's)
Address: RT. 1 BOX 49 BA TYRONE, OK 73951 Phone: (580) 854-6515

Proposed Date and Hour of Plugging (if known?): 11-1-04

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/29/04 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market Room 2078, Wichita, Kansas 67202

10/04



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Elder & Vaughn Inc
PO Box 18938
Oklahoma City, OK 73118

October 04, 2004

Re: JACQUART #1-30
API 15-175-21784-00-00
W2 30-33S-32W, 2490 FSL 3960 FEL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor