

RECEIVED  
OCT 04 2004  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-065-00178-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7-7-1951

Well Operator: Paul Bowman Oil Company KCC License #: 31008 7/05

Address: 801 Codell Road City: Codell

State: Kansas Zip Code: 67663 Contact Phone: (785) 434-2633

Lease: Buss C Well #: 1 Sec. 13 Twp. 9 S. R. 22  East  West

SE - SE - NE Spot Location / QQQQ County: Graham

2310 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 259 Cemented with: 250 Sacks

Production Casing Size: 5 1/2 Set at: 3802 Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle 3801-3805

Elevation: 2288 ( G.L. /  K.B.) T.D.: 3806 PBTD: 2500 Anhydrite Depth: 1825  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): will cement well according to KCC Dist#4 instructions

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Louis D Bowman

Phone: (785) 434-2286

Address: 805 Codell Road City / State: Codell, KS

Plugging Contractor: Allied Cementing Inc KCC License #: 99996  
(Company Name) (Contractor's)

Address: Russell, KS Phone: (785) 483-2627

Proposed Date and Hour of Plugging (if known?): October 4, 2004

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Oct 1, 2004 Authorized Operator / Agent: Paul D. Bowman  
(Signature)


Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Company- ANDERSON-PRICHARD OIL CORP.  
 Farm- Buss "C" No. 1

SEC. 13 T. 9 R. 22W  
 SE SE NE

Total Depth. 3806 Corr.  
 Comm. 6-27-51 Comp. 7-7-51  
 Shot or Treated.  
 Contractor. Glenn W. Peel  
 Issued. 10-6-51

County Graham  
 KANSAS



CASING:  
 8 5/8" 259' cem. — 250 SK  
 5 1/2" 3802' cem. — 125 SK

Elevation. 2288 RB

Production. 207 BO / 22% water,  
 State Test

Figures indicate Bottom of Formations.

surface clay	260
shale	870
shale, shells	1050
sand, shale	1120
shale	1201
shale, shells	1780
anhydrite	1825
shale, shells	2100
shale, lime	2455
lime	2715
lime, shale	3560
lime	3804 RTD
Total Depth Corrected	
to	3806

Tops:  
 Anhydrite 1771  
 Heebner 3453  
 Lansing 3495  
 Arbuckle 3801

DP & CO to bottom. Swb 10  
 BOPH/4 hrs. 1600' off bottom.  
 Swb 15 BOPH/4 hrs. 1200' off  
 bottom. Ran tubing & rods.

8-1-51 P 118 BO w/no wtr /8 hrs.  
 8-2-51 P 15 BFPH (10% wtr)  
 8-3-51 P 240 BF (168 oil / 72 wtr  
 (30% wtr) /24 hrs.) Water  
 analyzed as Arbuckle water.  
 8-8-51 P 129 BO / 43 BE/18 hrs  
 (25% wtr)  
 8-9-51 P 225 BO / 137 BW/24 hrs.  
 8-10-51 P 88 BO / 38 wtr (30%) in 8 hrs.  
 8-14-51 State Test: 207 BO / 22% wtr  
 in 24 hrs.

Arbuckle 3801: Fair show w.free oil  
 Fair porosity; very slight odor.

RECEIVED  
 OCT 04 2004  
 KCC WICHITA

1  
78 100  
50  
1

2425

150 = 2 50 84  
500 ~~25~~



CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Bowman, Paul d/b/a Paul Bowman Oil  
801 Codell Road  
Codell, KS 67663

October 04, 2004

Re: BUSS C #1  
API 15-065-00178-00-00  
SESENE 13-9S-22W, 2310 FNL 330 FEL  
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely  
  
David P. Williams  
Production Supervisor