

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

SEP 21 2004

Form CP-1
September 2003

WELL PLUGGING APPLICATION

CONSERVATION DIVISION
WICHITA, KS

This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

API # 15 - 167-23258-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 8-03-04

Well Operator: Double Eagle Exploration, Inc. KCC License #: 6009
(Owner / Company Name) (Operator's)

Address: 800 W 47th St. Suite 318 City: Kansas City

State: MO Zip Code: 64112 Contact Phone: (316) 264 - 0422

Lease: Laubhan Well #: 1 Sec. 7 Twp. 14 S. R. 12 East West

SE - SE - NW Spot Location / QQQQ County: Russell

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 424 Cemented with: 200 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1690/1695 (G.L. / K.B.) T.D.: 3390 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot 25 sx of cement at 3324', fill hole with rotary mud to 800' and spot 25 sx of cement. Fill hole with rotary mud to 575' and spot 50 sx of cement. Fill hole with rotary mud to 40' and spot 10 sx of cement to surface and put 15 sx of cement in rathole.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jim Robinson

Phone: (316) 264 - 0422

Address: 221 S. Broadway City / State: Wichita KS 67202

Plugging Contractor: Berentz Drilling Company, Inc. KCC License #: 5892
(Company Name) (Contractor's)

Address: PO Box 782228 Wichita KS 67278-2228 Phone: (316) 685 - 5908

Proposed Date and Hour of Plugging (if known?): 3:00 p.m. on 8-14-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-20-04 Authorized Operator / Agent: Jim Robinson
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/05

6/05