

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 199-20117-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 9/87

33136 11/04

Well Operator: Anadarko E&P Company LP KCC License #: 6417
(Owner/Company Name) (Operator's)

Address: P. O. Box 1330 City: Houston

State: TX Zip Code: 77251-1330 Contact Phone: 832 636-3128

Lease: Akers "A" Well #: 1 Sec. 12 Twp. 15 R. 43 East West

CS E SW SE Spot Location/QQQQ County Wallace

330 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

1382 930 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other _____

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 25 2004
CONSERVATION DIVISION
WICHITA, KS

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 514' Cemented with: 410 Sacks

Production Casing Size: 4-1/2" Set at: 5300' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 5120'-5125'

Elevation: 3936' (G.L. K.B.) T.D. 5300' PBDT 5245' Anhydrite Depth _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump 2 sxs of hulls and 40 sxs of H cement at 4800'. If packer cannot be removed, pump 9 sxs of cement down tubing. Cut off tubing and set cement plugs at 2605' to 2850', 355' to 600', and 4' to 50'. Cut off and cap 8-5/8" casing at 4'.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log was submitted with ACO-1.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Herschel Kennedy Phone: 719 767-8851

Address: 15562 Highway 385 City/State Cheyenne Wells, CO 80810

Plugging Contractor Eastern Colorado Well Service LLC KCC License # 32997
(Company Name) (Contractor's)

Address 43400 Hwy 40, PO Box 244, Cheyenne Wells, CO. 80810 Phone: 719-767-5100

Proposed Date and Hour of Plugging (If known?): 5-14-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-25-04 Authorized Operator / Agent: Jerry N. Blossom
(Signature)

Jerry N. Blossom