

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
September 2003  
Form must be Typed  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 199-20023--00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 2/28/78

Well Operator: Anadarko E&P Company LP KCC License #: 33136  
(Owner/Company Name) (Operator's)

Address: P. O. Box 1330 City: Houston

State: TX Zip Code: 77251-1330 Contact Phone: 832 636-3128

Lease: Johannes Well #: 1 Sec. 18 Twp. 15 R. 42  East  West

C - NE Spot Location/QQQQ County Wallace

~~39601320~~ Feet from (in exact footage)  North /  South (from nearest outside section corner) Line of Section (not Lease Line)

1320 Feet from (in exact footage)  East /  West (from nearest outside section corner) Line of Section (not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 25 2004  
CONSERVATION DIVISION  
WICHITA, KS

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 13-3/8" Set at: 564' Cemented with: 475 Sacks

Production Casing Size: 4-1/2" Set at: 5248' Cemented with: 410 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 5112'-5116'

Elevation: 3922' ( G.L.  K.B.) T.D. 5248' PBDT 5202' Anhydrite Depth \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Bullhead 2 sxs hull and 40 sxs H cement on  
perfs. Spot plug at 2655'-2900'. Perf from 633'-665' and set packer at 400' set cement plug from 461'  
to 665'. Spot cement plug from 4' to 50'. Cut off and cap 8-5/8" casing at 4'. Space plugs with 9 ppg.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Log was submitted with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Herschel Kennedy Phone: 719 767-8851

Address: 15562 Highway 385 City/State Cheyenne Wells, CO 80810

Plugging Contractor Eastern Colorado Well Service LLC KCC License # 32997  
(Company Name) (Contractor's)

Address 43400 Hwy 40, PO Box 244, Cheyenne Phone: 719-767-5100  
Wells, CO 80810

Proposed Date and Hour of Plugging (If known?): 5-14-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-25-04 Authorized Operator / Agent: Jerry N. Blossom  
(Signature)

Jerry N. Blossom