



15-137-20035-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1970
CONSERVATION DIVISION
Wichita, Kansas
6-25-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: B. E. Shelton,

Complete Address: 102 Insurance Building, Wichita, Kansas.

Lease Name: Doolittle Well No. 1

Location: CSW-SW Sec. 23 Twp. 4 Rge. (E)(W) 23

County: Norton Total Depth 3830' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Adams was instructed to plug the well as follows:

286'--8 5/8" Surface casing, cement circulated with 175 Sx.
3825'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 3350'. Top perforations @ 3324'.

Sand well back to 3300' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent