



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc. & Lario Oil & Gas Co.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Doolittle Well No. 1

Location: CSW-SW Sec. 23 Twp. 4 Rge. (E)(W) 23

County: Norton Total Depth 3830' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

287'--8 5/8" Surface casing. cement circulated with 175 Sx.
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1360' and displace 100 Sx.
cement thru DP from 1360' to 1035'. Pull DP to 285' and displace 20 Sx.
cement thru DP from 285' to 225'. Pull DP, set bridge @ 40' with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Rec'd
10-14-69

W. L. Nichols
Conservation Division Agent