



15-137-20036-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas

11-6-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Poe of Lario Oil & Gas Co., has this date requested permission to plug the following described well:

Mr. Poe guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company,

Complete Address: 301 South Market, Wichita, Kansas.

Lease Name: Arthur L. Henry Well No. 1

Location: 100' North of GE/2-NE-NE Sec. 10 Twp. 4 Rge. (E)(W) 23

County: Norton Total Depth 3678' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Poe was instructed to plug the well as follows:

273'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent