



15-137-20053-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

1-7-71  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: A. Ainsworth,

Complete Address: 310 Brown Building, Wichita, Kansas.

Lease Name: Harting Well No. 5

Location: NW-NW-SW Sec. 2 Twp. 4 Rge. (E)(W) 23

County: Norton Total Depth 3706 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3696'--5 1/2" Production casing cemented on bottom with 75 Sx. Open hole completion.

Sand well back to 3675' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squee well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent