



15-137-20080-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1972

CONSERVATION DIVISION  
Wichita, Kansas

7-7-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of J. O. Farmer, Inc. has this  
date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W. Wichita, Ks.

Lease Name: Harting Well No. 1

Location: SE SE Sec. 11 Twp. 4 Rge. (E)(W) 23

County: Norton Total Depth 3670' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 850' and displace  
100 cu ft of cmt. Heavy mud to 230' set cementing plug and displace  
30 cu ft of cmt. Heavy mud to 40' set cementing plug, 1/2 sk hulls and  
10 cu ft cmt to base of cellar.

Very truly yours,

Geo F. Massey  
Conservation Division Agent