

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20016-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name Nuttycomb Well No. 1

Location SW-NW-NE Sec. 11 Twp. 4 Rge. (E) (W) 21

County Norton Total Depth 3536'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:45 PM Day 7 Month 7 Year 1968

The Above well was plugged as follows:

192'--8 5/8" Surface casing, cement circulated.
3534'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3508'
Top perforations @ 3408'.

Sanded well back to 3400' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and
squeezed well initially with 5 sacks hulls plus 12 sacks gel then 100 Sx. cement from
1075' to 750' and followed with 13 sacks gel from 750' to 285' then 20 Sx. cement from
285 to 220' and followed with 5 sacks gel from 220' to 35' and finally 10 Sx. cement
from 35' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/12/68
INV. NO. 8089-W