

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15137-20022-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1969
CONSERVATION DIVISION
Wichita, Kansas
3-10-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name Martha M. Schick Well No. A-1

Location NW-NW-SW Sec. 11 Twp. 11 Rge. (E) (W) 21

County Norton Total Depth 3802'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Broken Arrow Drilling Company,

Address: Box #151, Great Bend, Kansas. License No. _____

Operation Completed: Hour 7:30 PM Day 11 Month 3 Year 1969

The Above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 90 Sx. cement thru DP from 1125' to 800'. Pulled DP to 245' and displaced 30 Sx. cement thru DP from 245' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels
Well Plugging Supervisor

INVOICED
DATE 3/10/69
INV. NO. 9440-W