

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20013-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas
7-12-68

Operator's Full Name National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name Roy Sides Well No. 1

Location CNW-SW Sec. 3 Twp. 4 Rge. (E) (W) 21

County Norton Total Depth 3769'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #105, Chase, Kansas. License No. 436

Operation Completed: Hour 10:30 AM Day 7 Month 7 Year 1968

The Above well was plugged as follows:

243'--8 5/8" Surface pipe, cement circulated.
3605'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
3567' Top perforations @ 3458'.

Sanded well back to 3450' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls plus 12 sacks gel then 100 Sx. cement
from 1075' to 750' and followed with 13 sacks gel from 750' to 285' then 20 Sx. cement
from 285' to 220' and followed with 5 sacks gel from 220' to 35' and finally 10 Sx.
cement from 35' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/12/68

INV. NO. 8088-W