

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-137-20094-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1974
7-8-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bell Brothers

Complete Address Box 581 Robinson, Illinois 62454

Lease Name Van Loenen, etal Well No. 1

Location NW SW NE Sec. 10 Twp. 4 Rge. (E) (W) 21

County Norton Total Depth 3770'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11 A Day XX 1 Month 7 Year 1974

The above well was plugged as follows:

RTD 3770' 8 5/8 csg set at 233' cwc 150 sk.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red J. Massey
Well Plugging Supervisor

DATE 7/10/74
INV. NO. 9474-W