

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-137-20021-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Norton SEC. 2 TWP. 4S RGE. 23 E/W  
 Location as in quarters or footage from lines:  
SW - SW - SW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Condor Energy, Inc.  
 Lease Name Harting Well No. #1  
 Office Address Box 108 Great Bend, KS 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): oil  
 Date Well Completed 1-14-69  
 Application for plugging filed 5-2-85  
 Plugging commenced 11:00 a.m. 5-8-85  
 Plugging completed 11:45 a.m. 5-8-85  
 Reason for abandonment of well or producing formation Excess

water, no oil  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel  
 Producing formation Regan Depth to top 3712 bottom 3713 T.D. 3743  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	165 sks			8 5/8 20#	201	0
Production	125 sks			4 1/2 9.5#	3743	1280


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet for each plug set. Bottom perf. was cemented with 100 sks cement prior to plugging.

Plugging: Down 8 5/8 casing at 300# max pressure.  
Mixed 8 sks hulls with 50 sks cement 20 sks gel  
100 sks cement 15 sks gel. Released plug.  
Mixed 50 sks cement. Shut well in.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co. Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Lawrence Chain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Lawrence Chain  
Edmwood, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of May, 1985

My Commission expires: 8-3-85

H. D. Boyd  
 Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION  
5-31-85  
 MAY 31 1985