



15-137-20016-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas
7-12-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Crandall of Knight Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: 4th Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name: Nuttycomb Well No. 1

Location: SW-NW-NE Sec. 11 Twp. 4 Rge. (E)(W) 21

County: Norton Total Depth 3536 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

192'--8 5/8" Surface pipe, cement circulated.

3534'--5 1/2" Prod uction casing cemented on bottom with 100 Sx. Well plugged back to 3508. Top perforations @ 3408.

Sand well back to 3400' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 sacks plus 5 sacks gel and 130 Sx. cement staged.

Very truly yours,

A. L. Nichols
Conservation Division Agent