

State of Kansas



15-137-20094-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1974
7-8-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wagner of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: Bell Brothers

Complete Address: Box 581 Robinson, Illinois

Lease Name: Van Loenen, etal Well No. 1

Location: NW SW NE Sec. 10 Twp. 4 Rge. (E)(W) 21

County: Norton Total Depth 3770' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red F. Massey
Conservation Division Agent