



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 10 1969
 CONSERVATION DIVISION
 Wichita, Kansas

3-10-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Charles Harre of Broken Arrow Drilling Co., has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name: Martha M. Schick Well No. A-1

Location: NW-NW-SW Sec. 4 Twp. 4 Rge. (E)(W) 21

County: Norton Total Depth 3802 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

206'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125 And displace 90 Sx.
cement thru DP. Pull DP to 245' and displace 30 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. S. Nichols
 Conservation Division Agent