

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-147-20,054-00-00

LEASE NAME Elsie-Jackson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 9

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 20 TWP. 4S RGE. 18W (E) or (W)

COUNTY Phillips

Date Well Completed 12/10/68

Plugging Commenced 5/12/97

Plugging Completed 5/12/97

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 5/11/97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? unknown If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3145' Bottom 3368' T.D. 3390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8"	205'	None
				4½"	3385'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Per'f well @ 1500' & 900'. Ran tubing to 1600' and pumped 160 sx 60/40 Pozmix, 10% gel w/400# hulls. Cement circulated. Pulled tubing out of hole and tied onto 4½" casing and pumped 50 sx same cement w/100# hulls. Max. pressure was 400#, w/200# shut-in pressure. Tied onto 4½" annulus and could not pump into it @ 400# pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corporation License No. 5128

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 97



Roxie VonLintel
Notary Public

My Commission Expires: 5-24-2001