

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DaMar Resources, Inc.
 Address: P. O. Box 70
 Phone: (785) 625-0020 Operator License #: 9067
 Type of Well: Oil Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10/14/04 *KCC* 10-14-04 (Date)
 by: Richard Lacey (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4330 Bottom: _____ T.D. 4359
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-20,231-00-00
 Lease Name: Maranville 'B'
 Well Number: 2
 Spot Location (QQQQ): SW NE - NW - SW *KCC*
1980 Feet from North / South Section Line
660 Feet from East / West Section Line
 Sec. 13 Twp. 20 S. R. 23 East West
 County: Ness
 Date Well Completed: 2/21/69
 Plugging Commenced: 10/4/04
 Plugging Completed: 10/4/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		282	surf	8 5/8	282	none
		4350	surf	5 1/2	4350	none

RECEIVED
OCT 14 2004
KCC-WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate @ 700' with two shots. Spot 25 sx common cement w/3% CC and 100# hulls @ 4300'. Spot 40 sx common w/3% CC.
Pump 150 sx 60/40 poz w/6% gel down 5 1/2 casing. Pump 10 sx poz down 5 1/2 - 8 5/8" annulus, pressure to 300#. Pump
additional 40 sx poz down 5 1/2". Fluid down 125'. Witnessed by Michael Maier

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
 Address: P. O. Box 466 Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
 State of Kansas County, Ellis, ss.


Curtis R. Longpine (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 12th day of October, 20 04

[Signature]
 Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]