

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
 Address: 100 S. Main, Suite 200, Wichita, KS 67202
 Phone: (316) 262-3596 Operator License #: 9408
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10/4/04 8/18/04 (Date)
 by: Virgil Clothier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 2824' Bottom: 2834' T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-20104-0000
 Lease Name: Pekarek
 Well Number: 5
 Spot Location (QQQQ): _____ - SE - NW - NE
990' Feet from North / South Section Line
1650' Feet from East / West Section Line
 Sec. 20 Twp. 14 S. R. 10 East West
 County: Ellsworth
 Date Well Completed: 10-6-04
 Plugging Commenced: 10-6-04
 Plugging Completed: 10-6-04

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Lansing | | 0 | 2894' | 5-1/2" | 2894' | 0 |
| | | | | | | |
| | | | | | | |

RECEIVED
OCT 14 2004
KCC WICHITA


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand casing to 2745'. Had welder cut off casing and install bored collar to cement. Spot 4 sx cement on sand. Perforate @ 1250', 850', 541' w/2 holes ea. Shut down. Cement to P&A - 35 sx @ 1275', 35 sx @ 850', 135 sx @ 315' Casing & surface pipe did circulate. Used 205 sx 60/40 pozmix, 4% gel.

Name of Plugging Contractor: Express Well Service License #: 6426
 Address: P.O. Box 19, Victoria, KS 67671-0019
 Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corp.
 State of Sedgwick County, Kansas, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
 (Signature) Gary Sharp
 (Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 13th day of October 2004
Glenna Lowe My Commission Expires: _____
 Notary Public



Mail to: KCC, Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bu