

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEREDCO INC.
Address: P O BOX 20380, WICHITA, KS 67208
Phone: (316) 265-3311 Operator License #: 5147
Type of Well: ENHR Docket #: E-3396
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 07/07/2004 (Date)
by: STEVE VANGIESON (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 3676 Bottom: 3714 T.D. 3714
TOPEKA Depth to Top: 2045 Bottom: 2078 T.D. 3714
TOPEKA Depth to Top: 1968 Bottom: 1980 T.D. 3714

API Number: 15-191-10084-00-01
X DRILLED 12/31/1936
Lease Name: WELLINGTON UNIT
Well Number: 70-1
Spot Location (QQQQ): NW SE W12 E12 SE KCC
1320 Feet from ☐ North / ☒ South Section Line BER
990 Feet from ☒ East / ☐ West Section Line 10-14-04
Sec. 32 Twp. 31 S. R. 1 ☐ East ☒ West
County: SUMNER
Date Well Completed: 2/09/1937
Plugging Commenced: 7/7/2004
Plugging Completed: 7/8/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	335	12.5	335	-0-
		0	3676	7"	3676	-0-
TOPEKA	SALTWATER					
MISSISSIPPI	OIL					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TD 3714' Sanded off to 3620', Dumped 10 sxs cement on top of sand with bailer. Ran 2 3/8" tubing to 385'. Got circulation, pumped 70 sxs 60/40 POZ + 4% gel to surface. Pulled 2 3/8" tubing out. Put 7" swedge on and pumped 35 sxs 60/40 POZ + 4% gel to 200#. Pumped 14 sxs 60/40 POZ + 4% gel. Shut in.

Name of Plugging Contractor: BEREDCO INC United Cementing License #: 5147 30437
Address: P O BOX 20380, WICHITA, KS 67208

Name of Party Responsible for Plugging Fees: BEREDCO INC.


State of KANSAS County, SEDGWICK, ss.

GARY MISAK

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Misak

(Address) BEREDCO INC., P O BOX 20380, WICHITA, KS 67208



Subscribed and SWORN TO before me this 13th day of October, 20 04
Diana E Plotner My Commission Expires: Aug 10, 2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUL 14 2004

C M F 14

United Cementing & Acid Company, Inc.

2510 W. 6th St.

El Dorado, Kansas 67042

316-321-4680 800-794-0187 (Fax) 316-321-4720

Remit Payment To:

One North Hudson, Suite 1000

Oklahoma City, OK 73102

405-278-8800

Customer:

Berexco, Inc.
PO Box 20380
Wichita, Kansas 67208

Invoice No. 6132

Field Ticket 5570

Date 7/13/2004

PO#

WU #70

Date of Job		County	State	Lease	Well No.
07/08/04		SU	KS	Wellington	#70
Size of Casing		Depth Of Well	Depth Of Job	Plug Depth	Pressure
7"		3714'			
Quantity	Description		Unit Price	Total	
	OLD HOLE PLUG		UOM		
119	60/40 Pozmix	sax	4.90	583.10	
5	Gel	sax	9.70	48.50	
124	Bulk Charge	sax	0.98	121.52	
	Drayage - 6.20 tons			262.51	
58	Mileage Charge	mi	2.05	118.90	
	Cement Unit			500.00	
<div>PEA'd well</div> <div>RECEIVED OCT 14 2004 KCC WICHITA</div> <div>Thank you for your continued business</div>					
Taxable		*Non-Taxable	Tax Rate	Sales Tax	TOTAL DUE
1634.53		0.00	0.053	86.63	\$1,721.16

P&A'd well

RECEIVED
OCT 14 2004
KCC WICHITA

TERMS: Net 30 days from invoice date. Please pay from this invoice.

ORIGINAL INVOICE



United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
(316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
2510 West 6th Street • El Dorado, KS 67042

SERVICE TICKET

✓ 5570

DATE 7-8-04

COUNTY Sumner CITY _____

CHARGE TO BereXco Inc.

ADDRESS PO Box 20380 CITY Wichita ST Ko. ZIP 67208

LEASE & WELL NO. Wellington #70 CONTRACTOR Jimenez Well Serv.

KIND OF JOB Old hole Plug SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. Wellington, 15 on 81 Hwy, 2 1/2 W, N Int. 11:00 OLD NEW

Quantity	MATERIAL USED	Serv. Charge
1195x	60/40 poz + 4% gel @4.90	500.00
55x	gel @9.70	583.10
		48.50
1245x	BULK CHARGE	121.52
58	BULK TRK. MILES <u>6.2 tons</u>	2102.51
58	PUMP TRK. MILES	118.90
	PLUGS	
	<u>.0530</u> SALES TAX	810.63
	TOTAL	1721.16

RECEIVED
OCT 14 2004
KCC WICHITA

T.D. 3714 ft.

SIZE HOLE _____

MAX. PRESS. _____

PLUG DEPTH _____

PLUG USED _____

CSG. SET AT _____ VOLUME _____

TBG SET AT _____ VOLUME _____

SIZE PIPE 7" casing

PKER DEPTH _____

TIME FINISHED 2:50

REMARKS: T.D. 3714ft. Sanded off to 3620ft. 105x cement on top of the sand "used the Rig" Ran Baler. Ran 2 3/8" tubing to 385ft Brake Circu. Mix & pump 705x 60/40 poz + 4% gel to surface. Pulled 2 3/8" tubing out. Put 7" swedge on mix & pump 355x 60/40 poz + 4% gel till PSI at 200#. Pumped another 145x 60/40 poz + 4% gel out after PSI & shut in.

EQUIPMENT USED

NAME _____ UNIT NO. _____

NAME _____ UNIT NO. _____

Chot Johnson P-14
James K Thomas #26
CEMENTER OR TREATER

Josh Creely B-7
OWNER'S REP.