

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 20 1988

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Stoneman

WELL NUMBER 9

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 4S RGE. 18 ~~XX~~or (W)

COUNTY Phillips

Date Well Completed Oct. 1965

Plugging Commenced 9/1/88

Plugging Completed 9/1/88

CONSERVATION DIVISION  
 Wichita, Kansas  
 LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/26/88 (date)

by Hays (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no-filed with application

Producing Formation Kansas City Depth to Top 3136' Bottom 3218' T.D. 3370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	oil			8-5/8"	205'	0
				4-1/2"	3369'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged back w/sand + 4 sx cement dumped w/bailer to 2800', Shot 4-1/2" @ 1500'+800'.  
Pulled 800' of 4-1/2" casing. Mixed 50 sx common, followed w/350 sx 60-40 Pozmix,  
8% gel-4 hulls #500 PSI. Shut in @ 200 PSI  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address 400 N. Woodlawn, Suite 201, Wichita, Kansas 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Steven P. O'Neill  
400 N. Woodlawn, Suite 201

SUBSCRIBED AND SWORN TO before me this 16th day of Sept, 19 88

[Signature]  
 Notary Public

My Commission Expires: 12/21/91

