

- STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-147-20,059-0001

LEASE NAME Elsie-Jackson

WELL NUMBER 10

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 04S RGE. 18W (E) or (W)

COUNTY Phillips

Date Well Completed 12.16.69

Plugging Commenced 5.12.03

Plugging Completed 5.12.03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5

Character of Well SWD - injection

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 5.11.03

by Jay Pfeifer

RECEIVED
JUN 13 2003
06-13-2003
KCC WICHITA

(KCC District Agent's Name).

Is ACO-1 Filed? ? ? If not, is well log attached? yes

Producing Formation L/KC Depth to Top 3146' Bottom 3372' T.D. 3406'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200'	None
				4 1/2"	3385'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran tubing to 2800' and pumped 140 sx of 60/40 Pozmix w/4 sacks of hulls. Cement circulated. Pulled tubing out and tied on to 5 1/2" casing and pumped 20 sacks of same cement. Pressured to 500#. Tied on to casing annulus and could not pump any cement into annulus. Shut in 500# PSI. Jay Pfeifer w/KCC witnessed the job.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 30606

Address 250 N. Water Suite 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 2003



[Signature]
Notary Public

My Commission Expires: 3/12/2005

ALLIED CEMENTING CO., INC. 11423

Federal Tax I.D.# ~~48-0727600~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

15-147-20059-00-01

SERVICE POINT: _____

R

DATE <u>5/12/03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:30 A.M.</u>	JOB START	JOB FINISH <u>11:30 A.M.</u>
LEASE <u>E. Jackson</u>		WELL# <u>109</u>		LOCATION <u>Glade 3w 1w 12w</u>		COUNTY <u>Phillips</u>	STATE <u>Ks</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR <u>Murfin</u>	OWNER _____
TYPE OF JOB <u>OND</u>	
HOLE SIZE _____ T.D. _____	CEMENT _____
CASING SIZE <u>4 1/2"</u> DEPTH _____	AMOUNT ORDERED <u>2600 w/ 40 100 lbs bags</u>
TUBING SIZE <u>2"</u> DEPTH _____	<u>5 Hauls</u>
DRILL PIPE _____ DEPTH _____	<u>USED 16000 4 1/2" x 13</u>
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>96</u> @ <u>7.15</u> <u>686.40</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>64</u> @ <u>3.00</u> <u>243.20</u>
CEMENT LEFT IN CSG. _____	GEL <u>11</u> @ <u>10.00</u> <u>110.00</u>
PERFS. _____	CHLORIDE _____ @ _____
DISPLACEMENT _____	<u>Hulls</u> <u>4</u> @ <u>18.00</u> <u>72.00</u>
EQUIPMENT	RECEIVED
PUMP TRUCK CEMENTER <u>Paul</u>	MAY 13 2003
# <u>3101</u> HELPER <u>Shane</u>	KCC WICHITA
BULK TRUCK _____	HANDLING <u>260</u>
# <u>3102</u> DRIVER <u>Glen</u>	MILEAGE <u>52.5k/mile</u>
BULK TRUCK _____	
# _____ DRIVER _____	TOTAL <u>2190.60</u>

REMARKS:	SERVICE
<u>The @ 2800' Circ. Cement w/</u>	DEPTH OF JOB _____
<u>14000 w/ 4 Hauls</u>	PUMP TRUCK CHARGE _____ <u>475.00</u>
<u>5/2 csg - 205x Press to scooper.</u>	EXTRA FOOTAGE _____ @ _____
<u>Shut in @ scooper.</u>	MILEAGE <u>60</u> @ <u>3.50</u> <u>210.00</u>
<u>Annulus - Cement in cellar</u>	PLUG _____ @ _____
	_____ @ _____
	_____ @ _____
	TOTAL <u>685.00</u>

CHARGE TO: R.P. Nixon

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT	
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
	TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____

RECEIVED
JUN 13 2003
KCC WICHITA