

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-200 33-00

LEASE NAME Stoneman

WELL NUMBER 11

1650 Ft. from S Section Line

480 Ft. from E Section Line

SEC. 20 TWP. 4S RGE. 18 (E or W)

COUNTY Phillips

Date Well Completed 5/68

Plugging Commenced 10-19-2000

Plugging Completed 10-19-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc

ADDRESS 14201 E. Central Wichita, Ks 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-18-2000 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Filed w/ Application

Producing Formation LKC Depth to Top 3032 Bottom 3289 T.D. 3334

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	0	203	8-5/8	198	0
		0	3333	4-1/2	3328	0

OCT 26 2000

10-26-2000

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Run tubing to 1500' Seat 50 SX Cement + 4 Halls. Pulled tubing to 950'
Circulate 50 SX Cement. Pulled tubing. Pump 10 SX Cement @ 700 PSL. Pumped
40 SX Cement down 8-5/8 - 4-1/2 Annulus. Shut in w/ 100 PSL. All Cement
60-40 202 + 1090 Gel

Name of Plugging Contractor Pfeifer Dozer & Well Service License No. 32,579

Address HCR 01 Box 63 St Peter Rt Moreland, Ks 67650

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF KANSAS COUNTY OF Sedgwick, ss.


GARY L. Reed Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Gary Reed

(Address) 14200 Brookline Ct. Wichita Ks 67230

SUBSCRIBED AND SWORN TO before me this 25 day of October, 2000

Dana R. Clothier
Notary Public



Expires: 11-13-2000

