

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20099-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1970
CONSERVATION DIVISION
Wichita, Kansas
7-14-70

Operator's Full Name Petroleum Management
Complete Address 1515 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Clark Well No. 1
Location NE SW SE Sec. 10 Twp. 4 Rge. (E) (W) 19
County Phillips Total Depth 2366
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 8 P Day 9 Month 7 Year 1970

The above well was plugged as follows:

RTD 2366' 8 5/8 csg set at 210' cwc Cmt. Mat. 100 sk reg poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk e
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/14/70
INV. NO. 2225-4

Signed: Leo J. M... [Signature]
Well Plugging Supervisor