

KANSAS

Form CP-3
Rev. 6-4-68

40
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20128-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas
9-9-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Weedman & Iannitti Oil Company

Complete Address 706 Union National Bldg., Wichita, Kansas

Lease Name Bach Well No. 1

Location C E/2 SE SE Sec. 4 Twp. 4 Rge. (E) (W) 19

County Phillips Total Depth 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 10:45 P Day 4 Month 9 Year 1971

The above well was plugged as follows:

RTD 3350' 8 5/8 csg set at 164' cwc 110 sk, Cmt. Mat. 50-50 per W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-10-71

INV. NO. 4313-W

Signed: Leo A. Massey
Well Plugging Supervisor