

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-147-19085-00-00

RECEIVED
STATE CORPORATION COMMISSION
7-29-75
JUL 29 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sierra Petroleum Company, Inc.

Complete Address Box 232, Russell, Kansas 67665

Lease Name Beckman Well No. A-1

Location C NW SE Sec. 3 Twp. 4 Rge. (E) (W) 19

County Phillips Total Depth 3450'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12:20 P Day 24 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3450' 8 5/8 csg set 207' cwc 150 sx.

4 1/2 csg set 3449' cw 125 sx cem.

4 1/2 csg PBD 3260' & perf. (3248)

Filled 4 1/2 csg W/snd (3260-3220) dumped 3 sx cem W/dump bailer. (3220-3190)

Cutoff & recovered 1520' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 15 sx gel & water W/300 lbs hulls -70 sx 50-50 poz

6% -15 sk gel & water -released 8 5/8 plug & pumped 50 sx cem. (50-50 poz 6%)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 7/30/75

INV. NO. 1689-W