

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-147-30096-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 10 1972  
10-10-1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name T. W. Jackson

Complete Address Phillipsburg, Kansas 67661

Lease Name Elsie Well No. 2

Location C E/2 SE SW Sec. 20 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3370'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling

Address Box 369 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10 A Day 6 Month 10 Year 1970

The above well was plugged as follows:

Total Depth 3370' 8 5/8 csg set at 240' cwc 150 sk.

4 1/2 csg set at 3367' cw 150 sk cmt.

4 1/2 csg perf. (3101-3278)

Set 4 1/2 wood plug at 3050' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3005-3050)

Cutoff and recovered 1410' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel \$ water W/500 lbs hulls, - 70 sk cmt, - 7 sk gel & water, - released 8 5/8 plug and pumped 50 sk cmt at 250 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murrey  
Well Plugging Supervisor

INVOICED  
DATE 10/11/72  
INV. NO. 6439-W