

KANSAS

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

NOV 12 1976

11-12-76

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -147-19099-00-00 (of this well)

Operator's Full Name T. W. Jackson

Complete Address Route #4, Phillipsburg, Kansas 67661

Lease Name Jackson Well No. 3

Location SE NW NE Sec. 20 Twp. 4 Rge. (E) (W) 16

County Phillips Total Depth 3544'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 11 Month 11 Year 1976

The above well was plugged as follows:

Total Depth 3544' 8 5/8 csg set 218' cwc 135 sx.

4 1/2 csg set 3411' cw 150 sx cem.

4 1/2 csg PBD 3364' with top perf. (3128')

Set 4 1/2 wood plug at 3000' -poured 10' sd -dumped 3 sx cem W/dump bailer. (3000'-2960')

Cutoff & recovered 1498' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs

hulls, released plug & 125 sx "Comm" 4% gel. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED

DATE 11-15-76

INV. NO. 4152-W