

KS
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20035-00-01

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1970
CONSERVATION DIVISION
Wichita, Kansas
6-25-70

Operator's Full Name B. E. Shelton.
Complete Address 102 Insurance Building, Wichita, Kansas.
Lease Name Doolittle Well No. 1
Location CSW-SW Sec. 23 Twp. 4 Rge. (E) (W) 23
County Norton Total Depth 3830'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Company, Incorporated,
Address Box #211, Great Bend, Kansas. License No. 49
Operation Completed: Hour 11:15 AM Day 23 Month 6 Year 1970

The above well was plugged as follows:

286'--8 5/8" Surface casing, cement circulated with 175 Sx.
3825'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 3350'. Top perforations @ 3324'.
Sanded well back to 3300' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 100 Sx. cement from 1100' to 775' then 12 sacks gel from 775' to 300' and followed with 20 Sx. cement from 300' to 240' then 5 sacks gel from 240' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--250#. Final shut-in pressure--50#. (Mudding and cementing operations by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Dickah*
Well Plugging Supervisor

INVOICED
DATE 6/25/70
INV. NO. 2119-W