

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20035-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1969
CONSERVATION DIVISION
Wichita, Kansas
10-14-69

Operator's Full Name Abercrombie Drilling, Incorporated & Lario Oil & Gas Company,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Doolittle Well No. 1

Location CSW-SW Sec. 23 Twp. 4 Rge. (E) (W) 23

County Norton Total Depth 3830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 PM Day 11 Month 10 Year 1969

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1360' and displaced 100 Sx. cement thru
DP from 1360' to 1035'. Pulled DP to 285' and displaced 20 Sx. cement thru DP from
285' to 225'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

10/14/69

INV. NO.

636-4

Signed:

W. L. Nichols
Well Plugging Supervisor