

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 137-20,150 0001

LEASE NAME Nuttycomb

WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4290 Ft. from S Section Line

1420 Ft. from E Section Line

SEC. 11 TWP. 4 RGE. 21 (W)

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS Box 428, Logan, Ks. 67646

PHONE# 913, 689-7456 OPERATORS LICENSE NO. 5352

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

COUNTY Norton

Date Well Completed 9-24-79

Plugging Commenced 6-13-90

Plugging Completed 6-13-90

The plugging proposal was approved on 6-12-90 (date)

by Dale F. Balthazor (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? -

Producing Formation K.C. Depth to Top 3411 Bottom 3602 T.D. 3621

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Shale	water	surf.	248	8-5/8	248'	none
Cedar Hills	water	surface	3620	4-1/2	3620	none
K.C.	oil & water	3411	3602	4-1/2	3620	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Ran tubing to 1800' & tagged plug back T.D. Pulled one jt. Pumped down tubing 100 sks. common cement. Pulled 700' of tubing. Pumped down 75 sks of cement 65-3 poz w/6% gel Pulled tbq. squeezed 15 sks of cement down csg. Locked up with 750# Pumped down 8-5/8" with 25 sks cement with 200#.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. -

Address P.O. Box 31, Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co., Inc.

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Baird Oil Co., Inc.


~~Employee or Operator~~ or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jane Baird Exec. V-Pres.

(Address) Box 428, Logan, Ks. 67646

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of JUNE, 19 90

Robert B. Hartman  
 Notary Public



Commission Expires: 3/29/91