

15-137-30071-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

NORTON

County. Sec. 26 Twp. 4 Rge. 21 (X) W (W)

Location as "NE/CNW/SW" or footage from lines APPROX C NE

Lease Owner DANE G HANSEN TRUST

Lease Name LUTZ-WILTROUT

Well No. 1

Office Address LOGAN, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed FEB 17, 1967

19

Application for plugging filed FEB 17, 1967

19

Application for plugging approved FEB 17, 1967

19

Plugging commenced FEB 17, 1967

19

Plugging completed FEB 17, 1967

19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3588 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	188.28'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD to 540'. SET
PLUG. PUT IN 20 SX CEMENT. FILLED
WITH HEAVY MUD TO 180'. SET PLUG.
PUT IN 1/2 SX HULLS AND 20 SX CEMENT.
FILLED WITH HEAVY MUD TO 40'. SET
PLUG. FILLED TO TOP WITH 1/2 SX
HULLS AND 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1967

2-27-67
CONSERVATION DIVISION

Name of Plugging Contractor C-G DRILLING COMPANY (If additional description is necessary, use BACK of this sheet)

Address 107 RULE BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK

JAY H GALLOWAY

(employee of owner) or (XXXXXX) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

JAY H GALLOWAY

107 RULE BUILDING

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of FEBRUARY, 1967

My commission expires JAN 23, 1968

Phyllis McJimsey
PHYLLIS MCJIMSEY

Notary Public.

15-137-30071-00-00

W E L L L O G

OPERATOR: DANE G HANSEN TRUST

WELL NAME: LUTZ-WILTROUT #1 LOCATION: APPROX C NE 26-4-21W

COUNTY: NORTON STATE: KANSAS

WELL COMMENCED: FEB 10, 1967 WELL COMPLETED: FEB 17, 1967

ELEVATION: 2078 KB TOTAL DEPTH: 3588'

PRODUCTION: DRY & ABANDONED RIG NO: #2

CASING - 8-5/8": 9 jts, 188.28' W/160 sx COMMON CEMENT + 200# CA. CL.

5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
188	750	SHALE	500' $\frac{1}{2}^{\circ}$	
750	950	SHALE & SAND	1000 $\frac{1}{4}^{\circ}$	
950	1180	SHALE	1500 $1\frac{1}{4}^{\circ}$	
1180	1410	SAND	1800 $3/4^{\circ}$	
1410	1714	SHALE	2500 $3/4^{\circ}$	
1714	1755	ANHYDRITE	3000 $3/4^{\circ}$	
1755	2520	SHALE & SHELLS		DST #1 3450-3485'
2520	3140	LIME & SHALE		DST #2 3479-3515'
3140	3588	LIME		

RECEIVED
STATE OF KANSAS
FEB 27 1967
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By

Jay H Galloway
JAY H GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 23rd day of FEBRUARY, 1967.

My comm. exp: Jan. 23, 1968

Phyllis McJimsey
Phyllis McJimsey ---Notary Public