


15-137-2011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Norton County, Sec. 26 Twp. 4 Rge. 21 EXW
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C/NE/NE
Lease Owner F & M Oil Company
Lease Name LUTZ-WILTROUT Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed June 14 1977
Application for plugging approved 19
Plugging commenced July 1 1977
Plugging completed July 14 1977
Reason for abandonment of well or producing formation
depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3664'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220'	none
				4 1/2"	3656'	1,516.17'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Dumped sand to 3450' and 3 sacks cement.
Shot pipe at 2800', 2500', 2000', 1800', 1600' and 1500'.
Pulled a total of 45 joints of 4 1/2" casing.
Plugged well with 3 sacks hulls, 70 sacks 50/50 Pozmix with 6% added gel,
3 sacks gel and 60 sacks 50/50 Pozmix with 6% added gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY of Barton, ss.
James W. Rockhold

(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.


(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July 1977

My commission expires May 21, 1980

Marla K. Haslam
Marla K. Haslam Notary Public.

RECEIVED
STATE CORPORATION COMMISSION



JUL 25 1977

CONSERVATION DIVISION
Wichita, Kansas

7-25-77

JUN 14 1977

CONTRACTOR'S WELL LOG 15-137-20111-00-00

OPERATOR: F & M Oil Co., Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: LUTZ-WILTROUT #1
 LOCATION: NE NE Section 26-4S-21W
 Norton County, Kansas
 SPUD DATE: July 15, 1976
 COMPLETION DATE: August 3, 1976

0	185	Clay & Sand
185	220	Shale
220	1150	Shale & Sand
1150	1290	Shale
1290	1490	Sand
1490	1773	Shale
1773	1802	Anhydrite
1802	2230	Shale
2230	2887	Shale & Lime
2887	3373	Lime & Shale
3373	3664	Lime
	3664	Rotary Total Depth

Drilled 220' of 12 1/4" hole, ran 5 jts. of used 8-5/8" 28# surface casing, tally 210', set @ 220' K.B., cement with 160 sx. quickset cement. Cement did circulate. Plug down 7:00 p.m. July 15, 1976. Shut down for vacation.

Ran 107 jts. of 4 1/2" used casing, set @ 3656' K.B. Cemented with 35 sx. 50/50 Posmix, 12 1/2# gilsinite, chase with 200 sx. common cement, 18% salt, 4# friction reducer. Plug down @ 2:00 a.m., August 3, 1976.

SAMPLE TOPS:

Anhydrite 1774' (+348)
 B/Anhydrite 1802' (+320)

JUN 15 1977 6-15-77

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the LUTZ-WILTROUT #1, NE NE, Section 26-4S-21W, Norton County, Kansas.


ABERCROMBIE DRILLING, INC.

BY: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 6th day of August, 1976.

Mildred Saxton
 Mildred Saxton, Notary Public

My Commission Expires: October 5, 1976.



COPY