

15-137-20113-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Norton County, Sec. 9 Twp. 4S Rge. 21W E/W  
Location as "NE/CNW<sup>1</sup>/SW<sup>1</sup>" or footage from lines  
SE NE NW

Lease Owner Bell Brothers  
Lease Name Keiswetter Well No. 1  
Office Address Box 581, 201 N. Jefferson, Robinson, Illinois  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
D & A  
Date Well completed December 17, 1976  
Application for plugging filed December 17, 1976  
Application for plugging approved December 17, 1976  
Plugging commenced December 17, 1976  
Plugging completed December 17, 1976  
Reason for abandonment of well or producing formation \_\_\_\_\_  
D & A



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,795'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Plug #1 @ 950' w/70 sx  
Plug #2 @ 270' w/20 sx  
Bridge @ 40' w/10 sx  
50-50 Pozmix, 6% Gel

DEC 30 1976  
12-30-76  
Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB&T Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gloria Fawcett (employee of owner) or (~~owner~~/~~op~~/~~operator~~)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB&T Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 76.

Joyce A. Hagermann  
Notary Public.

My commission expires \_\_\_\_\_



15-137-20113-00-00

DRILLERS LOG

No. 1 Keiswetter

CASING RECORD:

COMPANY: Bell Brothers

DESCRIPTION:

8 5/8" @ 273'  
w/200 sx cmt.

CONTRACTOR: Red Tiger Drilling Company

SE NE NW  
Sec. 9-T4S-R21W  
Norton County, Kansas

COMMENCED: December 8, 1976

COMPLETED: December 17, 1976

TOTAL DEPTH: 3,795'

ELEVATION: 2,218' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	277	
Shale	277	1400	
Sand	1400	1595	
Shale - Red Bed	1595	1875	
Anhydrite	1875	1905	
Red Bed & Shale	1905	2126	
Shale	2126	2696	
Shale & Lime	2696	2945	
Lime & Shale	2945	3050	
Lime	3050	3150	
Lime & Shale	3150	3401	
Lime	3401	3795	
RTD		3795	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 21st day of December, 1976.

Joyce A. Hagermann  
Notary Public

