

15-137-20146-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Norton County, Sec. 3 Twp. 4 Rge. 21WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/4 NW/4 SW/4

Lease Owner Baird Oil Company
Lease Name Sides Well No. 1
Office Address P.O. Box 7, Logan, Kansas 67646
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed June 1 1979
Application for plugging filed (verbally) June 1 1979
Application for plugging approved (verbally) June 1 1979
Plugging commenced June 1 1979
Plugging completed June 1 1979
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3690'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3690'

Set 1st plug at 950' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.

Cemented with 50/50 posmix, 6% gel.
Plug was down at 9:30 p.m., 6-01-79

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

CONSERVATION DIVISION
Wichita, Kansas

6-11-79

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June, 19 79



Sherrie L. Brooks

Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

15-137-20146-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Sides #1
LOCATION:	SE/4 NW/4 SW/4, Section 3-4-21W Norton County, Kansas
SPUD DATE:	May 25, 1979
COMPLETION DATE:	June 1, 1979

0	248	Clay, sand and shale
248	825	Shale and sand
825	1825	Sand and shale
1825	1887	Shale
1887	1917	Anhydrite
1917	2749	Shale
2749	3125	Shale and lime
3125	3461	Lime and shale
3461	3500	Lime
3500	3555	Lime and shale
3555	3600	Shale
3600	3651	Lime and shale
3651	3690	Lime
	3690	Rotary Total Depth

Spud hole at 6:45 p.m., May 25, 1979. Drilled 248' of 12 1/4" hole. Ran 6 joints of 8-5/8" new 20# casing. Set at 245' with 190 sacks of common cement, 3% ca.cl., 2% gel. Cement did circulate. Plug was down at 12:30 a.m., May 26, 1979.

T.D. 3690'. Set 1st plug at 950' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:30 p.m., May 1, 1979.

SAMPLE TOPS:

Anhydrite 1887'
B/Anhydrite 1917'

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1979

6-11-79

CONSERVATION DIVISION
WICHITA, KANSAS

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Sides #1, SE/4 NW/4 SW/4, Section 3-4-21W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 7th day of June, 1979.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 8-21-82.