

Casing Record

Norton County, Kansas

8-5/8" @ 394'

Allan & Aylward #1 Comstock
 SWc SW $\frac{1}{4}$ Sec. 3, T. 4S., R. 23W
 Commenced: 8/17/44 Completed: 9/4/44
 Contractor: Thos. H. Allan
 I. P. Dry & Abandoned
 Elevation: Floor 2451' L & S

- | | |
|--|--|
| <p>0 - 360 Tertiary sand
 394 gray chalky shale
 394 cemented 8-5/8" casing
 600 gray chalky shale
 650 white chalk (Ft. Hays)
 670 dark sandy pyritic shale
 790 blue shale
 830 buff calcitic lime
 910 dark blue shale
 1025 buff calcitic lime
 1060 buff concretions
 1150 fine white sand
 1240 red and gray sandy shale
 1280 sand
 1350 sandy shale
 1370 fine sand
 1430 gray shale
 1460 fine sand
 1490 gray shale
 1530 white sand
 1580 light green shale
 1610 white sand
 1670 red grit
 1850 fine white sand
 2080 red grit
 2112 white anhydrite
 2275 red shale
 2450 gray shale and anhydrite
 2580 red shale
 2610 red grit
 2730 shale & lime shells
 2750 white dolomitic lime
 2880 red shale
 2910 white dolomitic lime
 3280 red shale & lime shells
 3310 white lime with fusilinids
 3390 shale & lime shells
 3405 red shale
 3440 porous white lime
 3480 very soft red grit
 3490 red shale
 3500 white porous lime
 3525 shale & lime shells
 3550 lime with shale breaks
 3558 red & gray shale
 3560 black shale
 3565 lime
 3575 shale</p> | <p>3582 red shale
 3590 white lime
 3600 shale
 3615 white dense lime
 3625 red shale
 3630 porous white cherty lime (water)
 3659 shale & lime streaks
 3663 Oolitic lime S. S. oil (&water?)
 3685 dense white lime
 3695 cherty lime
 3705 shale
 3715 lime & shale streaks
 3720 porous brown oolitic lime (water)
 3735 red shale
 3745 porous lime (water)
 3750 red shale
 3780 white lime
 3790 red shale
 3800 red gritty shale
 3820 red shale & lime streaks
 3828 sandy lime S. S. dark oil
 3842 red shale & few large sand grains
 3865 porous sandy dolomite (water)
 3871 red & green mud
 3891 disintegrated granite
 3900 T. D. hard granite</p> |
|--|--|

FORMATIONS

- | | |
|--|---------------|
| <p>650 Base of Ft. Hays
 2080 Top Anhydrite
 3582 Top Lansing
 3842 Top Arbuckle
 3871 Top disintegrated granite</p> | <p>9-9-44</p> |
|--|---------------|

I certify that the above is a true and correct copy of the well log on the above test.

Thos. H. Allan

PLUGGING
 FILE REC-3 4 (23W)
 BOOK PAGE 30 LINE 38



15-137-00017-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA 2, KANSAS

IN REPLY PLEASE
REFER TO THIS
SUBJECT

September 9, 1944

Well No. 1
Farm Comstock
Description SW 3/4 SW 5-4-25W
County Norton
File 130-28

Mr. Thos. H. Allan
921 Union National Bank Bldg.
Wichita 2, Kansas

Dear Sir:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

JF

By:

J. P. Roberts
J. P. ROBERTS

NOTICE:

H. W. Kerr
Great Bend, Kansas