

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-147-20, 227-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Management, Inc. OPERATORS LICENSE NO. 5242  
ADDRESS 400 N. Woodlawn, Ste. 201 PHONE # (316) 686-7287  
Wichita, KS 67208  
LEASE (FARM) Beckman "B" WELL NO. 1 WELL LOCATION SW SE SE COUNTY Phillips  
SEC. 3 TWP. 4 RGE. 19W (E) or (W) TOTAL DEPTH 3445 PLUG BACK TD 3396

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8 5/8 SET AT 242' CEMENTED WITH 175 SACKS  
CASING SIZE 4 1/2" SET AT 3444 CEMENTED WITH 250 SACKS  
PERFORATED AT 3208-12, 3244-48, 3268-72, 3286-90, 3359-63

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand back perfs, dump bail 5 sx cmt.  
Pull casing @ ±1000'. Pump 250 sx cement down 8 5/8" casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACCO-1 FILED? N/A  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN September 4, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Don Keener PHONE # (913) 434-2042

ADDRESS Box H Plainville, KS 67663

PLUGGING CONTRACTOR Petroleum Management, Inc. LICENSE NO. 5242

ADDRESS Box H Plainville, KS 67663 PHONE # (913) 434-2042

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steven P. O'Neill Steven P. O'Neill  
(Operator or Agent)

DATE: August 17, 1989

④

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 21 1989  
8-21-89  
CONSERVATION DIVISION  
Wichita, Kansas

6/90

6/90

15-147-2 0227-00-00

DRILLERS LOG

No. 1 Beckman "B"

CASING RECORD:

COMPANY: Petroleum Management, Inc.

DESCRIPTION:

8 5/8" @ 242'  
w/175 sx cement

CONTRACTOR: Red Tiger Drilling Company

SW/4 SE/4 SE/4  
Sec. 3-T4S-R19W  
Phillips County, Kansas

4 1/2" @ 3,444'  
w/250 sx cement

COMMENCED: July 19, 1977

COMPLETED: July 25, 1977

TOTAL DEPTH: 3,445'

ELEVATION: 2,013 GR

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay, Shale	0	248	
Shale	248	1060	
Sand	1060	1245	
Shale	1245	1524	
Anhydrite	1524	1554	
Red Bed & Shale	1554	1745	
Shale	1745	2260	
Shale & Lime	2260	2562	
Shale	2562	2885	
Lime & Shale	2885	2998	
Lime	2998	3065	
Shale & Lime	3065	3180	
Lime	3180	3445	
RTD		3445	

RECEIVED  
STATE GEOLOGICAL COMMISSION  
AUG 21 1977  
821-89  
CONSERVATION DIVISION  
Wichita, Kansas


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 1st day of August, 1977.

Joyce A. Hagermann  
Notary Public



State of Kansas



15-147-20227-00-00

Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE  
NOV 21 1989  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

August 21, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Petroleum Management, Inc.  
400 N. Woodlawn, Ste 201  
Wichita, KS 67208.

Beckman "B"1  
SW SE SE  
03-04-19W  
Phillips County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200