

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM 15-039-00017-0000

Lease Owner Lamar Hunt Trust Address Shreveport, Louisiana

(Applicant)

Lease (Farm Name) Petracek Well No. 1

Well Location C. NE/4 NE/4 Sec. 14 Twp. 4 Rge. (E) or (W) 27

County Decatur Field Name (if any) _____

Was well log filed with application? yes. If not, explain: _____

Date and hour plugging is desired to begin July 3, 1948

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

Roy S. McClure Address Box 163, Great Bend, Kansas


Name of Plugging Contractor J. D. Ferrell Drilling Company, Inc.

Address Box 163, Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to:

J.D. Ferrell Drlg. Co., Inc. Address Box 163, Great Bend, Kansas

and payment will be guaranteed by applicant.



C. M. Roberson
JUL 15 1948
Applicant or Acting Agent

C. M. ROBERSON, Drilling Superintendent

Date July 12, 1948

15-039-00017-00-00

WELL LOG

LAMAR HUNT TRUST
Petracek #1

SEC. 14 T.4S R.27W
C NE/4 NE/4
County: Decatur
State: Kansas

Total Depth: 4020'
Comm: 6-16-48 Comp: 7-2-48
Contractor: J.D. Ferrell Drlg. Co. Inc.
Issued: 7-7-48 Rotary: 0-4020'

Elevation: 2594'
Production: Dry

Casing:

234' 10 3/4" Casing cem. w/150 sax cement.

Figures Indicate Bottom of Formations

cellar	0-5
clay & sand	80
sand & gravel	110
shale, post rock, sand	190
gyp & shale	234
black shale & sand	380
dark grey shale	425
shale	530
shale & shells	885
grey shale	1100
sandy lime & shale	1190
shale & shells	1530
sand	1585
shale & shells	1595
shale, shells & sand	1750
shale, shells & redbed	2015
shale & shells	2150
anhydrite	2190
shale & shells	2520
shale & lime	2755
shale & shells	2870
shale & lime	2895
lime	2955
sticky shale	2995
shale & chalk lime	3015
lime & shale	3090
lime	3175
shale & lime	3240
lime	3352
broken lime	3425
lime	3440
lime & shale	3460
lime	3495
broken lime	3535
lime	3644
lime (Dense)	3680
lime	3758
sandy shale	3770
lime & shale	3840
shale (red & sticky)	3907
lime & shale	3930
sandy shale	3944
sand & weathered granite	3950
conglomerate	3988
arbuckle lime	4020
Total Depth	4020

Tops:

Anhydrite	2150
Kansas City	3471
Arbuckle Lime	3988




We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

J. D. FERRELL DRILLING COMPANY

By J. W. Rubenack
Subscribed and sworn to before me this 9 day of July 1948.

My Commission expires:



Dale V. Sandefur
NOTARY PUBLIC



15-039-00017-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

July 6, 1948

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 1
Lease Potomac
Description C NE NE 14-4-27N
County Decatur
File: 41-26

J. D. Perrell Drilling Co.
Box 169
Great Bend, Kas.

Dear Sir:

This letter is your permit to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission.

Very truly yours,

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: H. A. Rives
Box 105
Hays, Kas.