

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

15-147-19097-00-00

6/88

API Number June 25, 1952 (of this well) (This must be listed; if no API# was issued, please note drilling completion data.)

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Slinker Unit WELL NO. 501 WELL LOCATION 2310' FWL CO. Phillips
~~330' FNL 4950' FEL~~
2970' FEL

SEC. 36 TWP. 4S RGE 20 (W) Total Depth 3313' PLUG BACK TD 3081'

CHECK ONE:

OIL WELL X GAS WELL D & A SWD OR INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 205' CEMENTED WITH 150 SACKS

CASING SIZE 5-1/2" SET AT 3313' CEMENTED WITH 150 SACKS

PERFORATED AT 3081-3266' (9-sets perforations)

CONDITION OF WELL: GOOD POOR X CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Refer to KCC field approved plugging procedure.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? Completed 1952

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: UNKNOWN AT THIS TIME.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

NAME J. D. Hininger PHONE # (913) 674-2182
ADDRESS Cities Service Oil and Gas Corp.
P. O. Box 38
Hill City, Kansas 67642

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
2-24-88

PLUGGING CONTRACTOR Unknown at this time LICENSE NO.
ADDRESS PHONE # ()

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill
(Operator or Agent)
DATE: 2-5-88

4



CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

15-147-19097-00-00

February 3, 1988
Wichita, Kansas

TO: Mr. M. D. Harrison
FROM: Mr. P. W. Pringle
SUBJECT: PLUGGING PROCEDURE.....SLINKER UNIT #501
330' FNL-2310' FWL
SECTION 36-T4S-R20W
PHILLIPS COUNTY, KANSAS

WELL DATA:

8-5/8" SURFACE CSG AT 205' W/150 SX
5-1/2" PRODUCTION CSG. AT 3313' W/150 SX
PERFORATIONS: 3081-3266' (9 SETS)
LAST SLM (1977) = 3081'

SHALLOW FORMATION DATA:

DAKOTA 540-850'
CHEYENNE 930-960'
ANHYDRITE 1455-1490'

PLUGGING PROCEDURE APPROVED BY MR. DENNIS HAMEL (1/22/88)

- 1) Prior to plugging, contact Mr. Hamel at KCC district office #4 Hays, Kansas (phone No. 913-628-1200).
- 2) Perforate at 3000' with 3 SPF, perforate above the Anhydrite at 1445' with 4 SPF, perforate below the Dakota at 860' with 3 SPF and perforate the surface casing at 205' with 3 SPF.
- 3) Tie onto the 5-1/2" casing and fill up the long pipe from 3000' to surface and casing annulus to surface with cement, Hulls and Flocele. (Approximately 300 sx cement, 5 sx Hulls and 75# Flocele).
- 4) Let cement sit 48 hrs., check T.O.C. and cap well.

Note: Cement calculations based on 65/35 cement with 10% gel + 2% Econolite additive. Slurry volume 3.62 ft.³/sx, blend ratio 23 gals wtr/sx. Also add 1/4# Flocele/sx of slurry.

PWP/mlf



15-147-19097-00-00

Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI M. FEIST, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE
 MAY 29 '88
 EXPIRES

February 29, 1988

WELL PLUGGING NOTICE

Slinker Unit #501
 4950' FSL 2970' FEL
 Sec. 36-04S-20W
 Phillips County

Cities Service Oil & Gas Corporation
 3545 NW 58th Street
 Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

 Shari Feist
 Director
 State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200