

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-147-20288-00-00 (of this well)
Lease Owner Baird Oil Company, Inc.
Address Box 7, Logan, Kansas 67646
Lease (Farm Name) ZINK Well No. 1
Well Location SE NE NW Sec. 27 Twp. 4S Rge. 20 (E) (W) X
County Phillips Total Depth 3374' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 12:30 p.m. 09-04-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 S. 2nd Street, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to: _____

Name Baird Oil Company, Inc.

Address Box 7, Logan, Kansas 67646

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Jack L. Partridge, Asst. Sec.-Treas.

Date: 09-09-80

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1980
CONSERVATION DIVISION
Wichita, Kansas

9-11-80

15-147-20288-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	ZINK #1
LOCATION:	SE NE NW, Section 27-4S-20W Phillips County, Kansas
SPUD DATE:	08-27-80
COMPLETION DATE:	09-04-80

0	1548	Shale & Sand
1548	1579	Anhydrite
1579	2900	Shale
2900	3177	Lime & Shale
3177	3374	Lime
	3374	Rotary Total Depth

Spud hole @ 2:30 p.m. 08-27-80. Drilled 215' of a 12-1/4" hole. Ran 5 joints of 8-5/8" - 20# casing (tally 206.25) Set at 214.75'. Cemented with 180 sx. of common, 2% gel, 3% c.c. Plug was down @ 8:00 p.m. 08-28-80.

T.D. 3374'. Plugging orders: Set 1st plug @ 900' with 70 sx., 2nd plug @ 210' with 25 sx., 3rd plug @ 40' solid bridge, rathole with 5 sx. 50/50 posmix, 6% gel. State plugger was Marion Schmidt. Plug was down @ 12:30 p.m. 09-04-80.

SAMPLE TOPS:

Anhydrite	1548'
B/Anhydrite	1579'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1980

CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the ZINK #1, SE NE NW, Section 27-4S-20W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 10th day of September 1980.

Jeanette A. Metheny
Jeanette A. Metheny, Notary Public

State of Kansas



15-147-20288-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

September 12, 1980

WELL PLUGGING AUTHORITY

Zink #1
SE NE NW, Sec.27-4S-20W
Phillips
3375'
Abercrombie Drilg. Co., Inc.


Baird Oil Company, Inc.
Box 7
Logan, KS 67646

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS 67601

is hereby assigned to supervise the plugging of the above named well